IAP/ Rec'd PCT/PTO 11 JUL 2006

Approved for use through 07/31/2006. OMB 0651-0031 U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number Application Number 10/580,557 TRANSMITTAL Filing Date 26 May 2006 First Named Inventor Benjamin Liu **FORM** Art Unit Not Yet Assigned **Examiner Name** Not Yet Assigned (to be used for all correspondence after initial filing) Attorney Docket Number 42390P22191 Total Number of Pages in This Submission **ENCLOSURES** (Check all that apply) After Allowance Communication to TC Fee Transmittal Form Drawing(s) Appeal Communication to Board Licensing-related Papers Fee Attached of Appeals and Interferences Appeal Communication to TC Petition (Appeal Notice, Brief, Reply Brief) Amendment/Reply Petition to Convert to a **Proprietary Information** After Final Provisional Application Power of Attorney, Revocation Status Letter Affidavits/declaration(s) Change of Correspondence Address Other Enclosure(s) (please Identify Terminal Disclaimer **Extension of Time Request** below): Return Receipt Postcard Request for Refund **Express Abandonment Request** CD, Number of CD(s) Information Disclosure Statement Landscape Table on CD Certified Copy of Priority Remarks Express Mail No. EV 841 072 613 US Document(s) Reply to Missing Parts/ Incomplete Application Reply to Missing Parts under 37 CFR 1.52 or 1.53 SIGNATURE OF APPLICANT, ATTORNEY, OR AGENT BLAKELY, SOKOLOFF, TAYLOR & ZAFMAN, LLP Firm Name 12400 Wilshire Boulevard, Seventh Floor, Los Angeles, California 90025-1030 Signature Printed name James C. Scheller Date Reg. No. 31,195 7 00 **CERTIFICATE OF MAILING** I hereby certify that this correspondence is being deposited with the United States Postal Service with sufficient postage as first class mail in an envelope addressed to: Mail Stop PCT, Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450 on the date shown below: usuca Signature Date Jessica Savagé 7/11/2006 Typed or printed name

This collection of information is required by 37 CFR 1.5. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.11 and 1.14. This collection is estimated to 2 hours to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: MS PCT, Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.

中华人民共和国国家知识产权局 STATE INTELLECTUAL PROPERTY OFFICE OF THE PEOPLE'S REPUBLIC OF CHINA



证明

CERTIFICATE

本证明之附件是向中国专利局作为受理局提交的下列国际申请副本 IS TO CERTIFY THAT ANNEXED HERETO IS A TRUE COPY OF THE BELOW ENTIFIED INTERNATIONAL APPLICATION THAT WAS FILED WITH THE CHINESE PATENT OFFICE AS RECEIVING OFFICE

申请号:

PCT/CN2005/002304

ATIONAL APPLICATION NUMBER

申请日:

23.12月 2005 (23.12.2005)

TILNAL FILING DATE

名 称:

MANAGING DEVICE MODELS IN A VIRTUAL MACHING

INVENTION

CLUSTER ENVIRONMENT

CERTIFIED COPY OF PRIORITY DOCUMENT

中华人民共和国国家知识产权局局长
COMMISSIONER OF THE STATE INTELLECTUAL PROPERTY
OFFECE OF THE PEOPLE'S REPUBLIC OF CHINA

田为等

二零零六年五月十七日 MAY 17. 2006



PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

	International Application vo.
ე	ֆրել արագրայան 1944-1951-1951-1951-1951-1951-1951-1951-
4	PO/CN 中华人民共和国国家知识产权局PCT International Application
	Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference (if desired) (12 characters maximum) FPEL05150068

1	(if desired) (12 character	rs maximum) FPE	L05150068		
BOX NO. I TITLE OF INVENTION MANAGING DEVICE MODELS IN A VIRTUAL M	ACHINE CLUST	ER ENVIRON	MENT		
Box No. II APPLICANT This person	is also inventor				
Name and address: (Family name followed by given name; for a legal entity The address must include postal code and name of country. The country of the Box is the applicant's State (that is, country) of residence if no State of residence	e agaress indicated in into	Telephone No.			
INTEL CORPORATION	o is indicated with the	Facsimile No.			
2200 Mission College Blvd.					
Santa Clara, California 95052		Teleprinter No.			
United States of America		A licent's regist	ration No. with the Office		
		Applicant stegist	ration 140. with the Office		
State (that is, country) of nationality: US	State (that is, country) US	of residence:			
This areas is applicant all designated and all designated		the United States of America only	the States indicated in the Supplemental Box		
Box No. III FURTHER APPLICANT(S) AND/OR (FURTH	IER) INVENTOR(S)	.			
Name and address: (Family name followed by given name; for a legal enti. The address must include postal code and name of country. The country of the Box is the applicant's State (that is, country) of residence if no State of residence LIU, Benjamin Room 302, No. 264 South Shanxi Road Shanghai 200001 P. R. of China	ce is indicated below.)	inventor marked, Applicant's regis	t only t and inventor only (If this check-box is do not fill in below.) tration No. with the Office		
State (that is, country) of nationality:	State (that is, country,	of residence:			
This person is applicant all designated all designates	d States except tates of America	the United States of America only	the States indicated in the Supplemental Box		
Further applicants and/or (further) inventors are indicated of	on a continuation sheet.				
Box No. IV AGENT OR COMMON REPRESENTATIVE	; OR ADDRESS FOR	CORRESPOND	ENCE		
The person identified below is hereby/has been appointed to act of the applicant(s) before the competent International Authorities	on behalf x as:	agent	common representative		
Name and address: (Family name followed by given name; for a legal ent The address must include postal code and name of c	ity, full official designation. country.)	Telephone No. (852)2828	4688		
China Patent Agent (H.K.) Ltd.		Facsimile No.			
22/F, Great Eagle Centre		(852)2827	1018		
23 Harbour Road, Wanchai Hong Kong Special Administrative Region		Teleprinter No.			
The People's Republic of China			a'>Tial-a) - Offi		
The reopie's republic of State		Agent's registra	tion No. with the Office		
Address for correspondence: Mark this check-box where space above is used instead to indicate a special address to	e no agent or common re which correspondence	epresentative is/has should be sent.	s been appointed and the		

Sheet No. ...?

Continuation of Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S) If none of the following sub-boxes is used, this sheet should not be included in the request.				
Name and address: (Family name followed by given name; for a legal entity, full office The address must include postal code and name of country. The country of the address is Box is the applicant's State (that is, country) of residence if no State of residence is indicated LING, Xiaofeng Room 201, 2# Bldg, No. 61 Haiting Road Shanghai 201204	ial designation. This person is:			
P. R. of China	Applicant's registration No. with the Office			
State (that is, country) of nationality: CN State (the CN)	hat is, country) of residence:			
This person is applicant all designated states except for the purposes of: all designated the United States of Am	efica of America only the Supplemental Box			
Name and address: (Family name followed by given name; for a legal entity, full offici The address must include postal code and name of country. The country of the address in Box is the applicant's State (that is, country) of residence if no State of residence is indicated JIANG, Yunhong Room 2107, No. 3 Lane 652 Daduhe Road Shanghai 200001 P. R. of China				
State (that is, country) of nationality: CN State (the CN)	nat is, country) of residence:			
This person is applicant all designated all designated States exceed the United States of American	the United States the States indicated in the Supplemental Box			
Name and address: (Family name followed by given name; for a legal entity, full official The address must include postal code and name of country. The country of the address in Box is the applicant's State (that is, country) of residence if no State of residence is indicate LI, Xin Room 302, No. 264 South Shanxi Road Shanghai 200001 P. R. of China	diamend Alice			
State (that is, country) of nationality: CN State (the CN)	at is, country) of residence:			
This person is applicant for the purposes of: all designated States exceptor the United States of American	pt the United States the States indicated in the Supplemental Box			
Name and address: (Family name followed by given name; for a legal entity, full officia The address must include postal code and name of country. The country of the address ina Box is the applicant's State (that is, country) of residence if no State of residence is indicated	designation. This person is:			
State (that is, country) of nationality: State (that	(is, country) of residence:			
This person is applicant all designated all designated States exceptor the purposes of: all designated the United States of American	t the United States the States indicated in the Supplemental Box			
Further applicants and/or (further) inventors are indicated on another continuation sheet.				

		She	eet No		, to		
Box No. V	DESIGNATI	ONS					
The filing of th filing date, for	is request cons the grant of ev	titutes under Rule 4.9(a), the ery kind of protection available	designation of all Contra le and, where applicable, i	ecting States bound by the for the grant of both region	PCT on the international onal and national patents.		
However,							
☐ DE Gerr	nany is not de	signated for any kind of nation	nal protection				
KR Rep	ublic of Korea	is not designated for any kin-	d of national protection				
		n is not designated for any ku					
(The check-boxes above may be used to exclude (irrevocably) the designations concerned in order to avoid the ceasing of the effect, under the national law, of an earlier national application from which priority is claimed. See the Notes to Box No. V as to the consequences of such national law provisions in these and certain other States.)							
Box No. VI	PRIORITY	CLAIM					
The priority of	the following	earlier application(s) is hereb	y claimed:				
Filing		Number		Where earlier application	is:		
of earlier a (day/mon	pplication	of earlier application	national application: country or Member of WTO	regional application:* regional Office	international application: receiving Office		
item (1)							
item (2)							
2	. <u>. </u>	-					
item (3)					·		
		1					
l —		are indicated in the Suppleme					
The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of this international application is the receiving Office) identified							
above as:		tem (1) item (2		· — .	see Supplemental Box		
* Where the a	earlier applicat operty or one N	tion is an ARIPO application, i Member of the World Trade O	indicate at least one count Organization for which that	ry party to the Paris Conv t earlier application was f	vention for the Protection of filed (Rule 4.10(b)(ii)):		
Box No. VII		TIONAL SEARCHING AU					
international	searcn, inaica	earching Authority (ISA) (if te the Authority chosen; the tw	0 :0::07 0000) ==,				
ISA / .CN							
Request to 1	se results of	earlier search; reference to	that search (if an earlier	search has been carried (nu by or requested from the		
	International Searching Authority): Date (day/month/year) Number Country (or regional Office)						
Box No. VIII DECLARATIONS							
The following declarations are contained in Boxes Nos. VIII (i) to (v) (mark the applicable check-boxes below and indicate in the right column the number of each type of declaration): Number of declarations							
Box N	Box No. VIII (i) Declaration as to the identity of the inventor						
Box N	Box No. VIII (ii) Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent:						
☐ Box N	Box No. VIII (iii) Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application:						
Box 1	Box No. VIII (iv) Declaration of inventorship (only for the purposes of the designation of the United States of America)						
☐ Box 1	Box No. VIII (v) Declaration as to non-prejudicial disclosures or exceptions to lack of novelty :				lty :		

C14 N1	r_			4		
Sheet N	ο.		٠	٠	٠	

Box No. IX CHECK LIST; LANGUAGE OF FILING					
This international application contains: a) in paper form, the following number of the following numb					
sheets:	1. The fee calculation sheet	: 1			
request (including declaration sheets) : 4	2. original separate power of attorney	: 1			
description (excluding	3. original general power of attorney	:			
sequence listing and/or tables related thereto) : 14	4 D conv. of general power of attorney; reference number.	1			
claims : 11	if any:				
abstract : 1	5. statement explaining lack of signature	•			
drawings : 6	6. priority document(s) identified in Box No. VI as item(s):	:			
Sub-total number of sheets : 36 sequence listing :	7. translation of international application into (language):	:			
tables related thereto : (for both, actual number of	8. separate indications concerning deposited microorganism or other biological material	:			
sheets if filed in paper form, whether or not also filed in	 sequence listing in computer readable form (indicate type and number of carriers) 				
computer readable form; see (c) below) —————	 (i) ☐ copy submitted for the purposes of international search under Rule 13ter only (and not as part of the international application 	ı):			
Total number of sheets : 36	(ii) (only where check-box (b)(i) or (c)(i) is marked in left column)				
(Section 801(a)(i)) (i) sequence listing	purposes of international search under Rule 13ter (iii) together with relevant statement as to the identity of the copy of copies with the sequence listing mentioned in left column	. 1			
(ii) ☐ tables related thereto (c) ☐ also in computer readable form	10. tables in computer readable form related to sequence listing (indicate type and number of carriers)				
(Section 801(a)(ii)) (i) ☐ sequence listing	(i) copy submitted for the purposes of international search under Section 802(b-quater) only (and not as part of the international search under Section 802(b-quater)	ıl			
(ii) tables related thereto	application) (ii) (only where check-box (b) (ii) or (c) (ii) is marked in left column)	:			
Type and number of carriers (diskette, CD-ROM, CD-R or other) on which are contained the	additional copies including, where applicable, the copy for the purposes of international search under Section 802(b-quater)				
sequence listing:	(iii) together with relevant statement as to the identity of the copy or copies with the tables mentioned in left column				
tables related thereto:	11. other (specify):	:			
(additional copies to be indicated under items 9(ii) and/or 10(ii), in right column)					
Figure of the drawings which should accompany the abstract:	Language of filing of the international application:				
THE PART OF A PRINCIPAL TO A PRINCIP	IT, AGENT OR COMMON REPRESENTATIVE griing and the capaging and vivide the person signs (if such capacity is not obvious from readin	g the request).			
Box No. X SIGNATURE OF APPLICANT, AGENT The person signs (if such capacity is not obvious from reading the request). Next to each signature, indicate the name of the person signing and the capacity the person signs (if such capacity is not obvious from reading the request). The person signs (if such capacity is not obvious from reading the request). The person signs (if such capacity is not obvious from reading the request). The person signs (if such capacity is not obvious from reading the request).					
For receiving Office use only					
1. Date of actual receipt of the purported international application: 2 3 · 12月 2005 (2 3 ° 1 2 ° 200 5)					
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:					
4. Date of timely receipt of the required corrections under PCT Article 11(2):					
5. International Searching Authority (if two or more are competent): ISA /	6. Transmittal of search copy delayed until search fee is paid				
For International Bureau use only					
Date of receipt of the record copy by the International Bureau:					

This sheet is not part of and does not count as a sheet of the international application.

PCT

FEE CALCULATION SHEET Annex to the Request

Form PCT/RO/101 (Annex) (January 2004)

For receiving Office use only

PCT/CN 2005 / 0 0 2 3 0 4

International Application No.

See Notes to the fee calculation sheet

	0 0 100 0000 00				
Applicant's or agent's file reference FPEL05150068	2 3 · 12月 2005 (2 3 · 1 2 · 2 0 0 5 Date stamp of the receiving Office				
Applicant INTEL CORPORATION etc.					
CALCULATION OF PRESCRIBED FEES	Co. 1 V 12 22 /				
1. TRANSMITTAL FEE	CNY500 T CNY600 CNY600				
2. SEARCH FEE International search to be carried out by (If two or more International Searching Authorities are competent international search, indicate the name of the Authority which is clithe international search.)	to carry out the				
3. INTERNATIONAL FILING FEE	·				
Where items (b) and/or (c) of Box No. IX apply, enter Sub-total nur Where items (b) and (c) of Box No. IX do not apply, enter Total nur	mber of sheets				
i1 first 30 sheets	CHF1400 [1] OHF1400				
i2 6 x CHF15 = representation of sheets in excess of 30	CHF1400 [i] OHF1400 [i] CHF90 [i2] CHF90 [i]				
additional component (only if sequence listing and/or tables re thereto are filed in computer readable form under Section 801 (or both in that form and on paper, under Section 801(a)(ii)):					
400 x =	CHF1 490 CHF1480				
Add amounts entered at i1, i2 and i3 and enter total at I (Applicants from certain States are entitled to a reduction of 75 international filing fee. Where the applicant is (or all applicants entitled, the total to be entered at I is 25% of the international filing	% of the s are) so				
4. FEE FOR PRIORITY DOCUMENT (if applicable)	- (λ/ Υ) (P)				
5. TOTAL FEES PAYABLE	CNY2000CHF149 CHF1480				
MODE OF PAYMENT					
authorization to charge coupons postal money order cash coupons					
cheque bank draft	revenue stamps other (specify):				
AUTHORIZATION TO CHARGE (OR CREDIT) DEPOSIT ACCOUNT (This mode of payment may not be available at all receiving Offices) Receiving Office: Receiving Office:					
Authorization to charge the total fees indicated above. (This check-box may be marked only if the conditions for deposit account of the receiving Office so permit) Authorization to charge any deficient or credit any overpayment in the total fees indicated above.					
Authorization to charge the fee for priority document.	Signature:				





MANAGING DEVICE MODELS IN A VIRTUAL MACHINE CLUSTER ENVIRONMENT

BACKGROUND

A virtual machine (VM) architecture logically partitions a physical machine, [0001] such that the underlying hardware of the machine is time-shared and appears 5 as one or more independently operation virtual machines. A computer platform in a virtual machine cluster environment may comprise a virtual machine monitor (VMM) that may create a plurality of virtual machines and runs on the computer platform to facilitate for other software the abstraction of one or more virtual machines. The computer platform may further comprise a plurality of 10 device models that may be virtualizations/simulations of real devices. The virtual machine monitor may manage resource usage for operations between the virtual machines and the device models, such as device related input/output operation and device model initiated interrupt. Examples for the virtual machine monitor may comprise a hybrid virtual machine monitor, a host 15 virtual machine monitor and a hypervisor virtual machine monitor. Examples for the real device may comprise various input/output (I/O) devices, an interrupt controller, and an event timer, etc.

BRIEF DESCRIPTION OF THE DRAWINGS

The invention described herein is illustrated by way of example and not by way of limitation in the accompanying figures. For simplicity and clarity of illustration, elements illustrated in the figures are not necessarily drawn to scale. For example, the dimensions of some elements may be exaggerated relative to other elements for clarity. Further, where considered appropriate,

reference labels have been repeated among the figures to indicate corresponding or analogous elements.

- [0003] Fig. 1 shows an embodiment of a virtual machine cluster environment.
- [0004] Fig. 2 shows an embodiment of structures of a server platform and a
- 5 plurality of client platforms in the virtual machine cluster environment of Fig. 1.
- [0005] Fig. 3 shows an embodiment of a method of implementing a device related input/output operation in the virtual machine cluster environment of Fig. 2.
- [0006] Fig. 4 shows an embodiment of a method of implementing a device model initiated interrupt in the virtual machine cluster environment of Fig. 2.
- 10[0007] Fig. 5 shows an embodiment of a computer platform that may be implemented as a platform within the virtual machine cluster environment of Fig. 2.
 - [0008] Fig. 6 shows another embodiment of structures of a server platform and a plurality of client platforms in the virtual machine cluster environment of Fig. 1.

15 **DETAILED DESCRIPTION**

- [0009] The following description describes techniques for managing device models in a virtual machine cluster environment. In the following description, numerous specific details such as logic implementations, pseudo-code, means to specify operands, resource partitioning/sharing/duplication implementations,
- 20 types and interrelationships of system components, and logic partitioning/integration choices are set forth in order to provide a more thorough understanding of the current invention. However, the invention may be practiced without such specific details. In other instances, control structures, gate level circuits and full software instruction sequences have not



been shown in detail in order not to obscure the invention. Those of ordinary skill in the art, with the included descriptions, will be able to implement appropriate functionality without undue experimentation.

References in the specification to "one embodiment", "an embodiment", "an [0010] example embodiment", etc., indicate that the embodiment described may 5 include a particular feature, structure, or characteristic, but every embodiment may not necessarily include the particular feature, structure, or characteristic. Moreover, such phrases are not necessarily referring to the same embodiment. Further, when a particular feature, structure, or characteristic is described in connection with an embodiment, it is submitted that it is within the 10 knowledge of one skilled in the art to effect such feature, structure, or characteristic in connection with other embodiments whether or not explicitly described.

Embodiments of the invention may be implemented in hardware, firmware, [0011] software, or any combination thereof. Embodiments of the invention may also 15 be implemented as instructions stored on a machine-readable medium, that may be read and executed by one or more processors. A machine-readable medium may include any mechanism for storing or transmitting information in a form readable by a machine (e.g., a computing device). For example, a machine-readable medium may include read only memory (ROM); random 20 access memory (RAM); magnetic disk storage media; optical storage media; flash memory devices; electrical, optical, acoustical or other forms of propagated signals (e.g., carrier waves, infrared signals, digital signals, etc.) and others.

- [0012] An embodiment of a virtual machine cluster environment 1 is shown in Fig.
 - 1. The virtual machine cluster environment 1 may comprise a plurality of client platforms 10/30 and a server platform 20 that may connect with the client platforms 10/30 through a network 40, such as Ethernet, fiber channel or other like communications link. In the embodiment, the virtual machine cluster environment 1 may comprise any number of client platforms and server
- [0013] Each of the client platforms 10/30 may host a plurality of virtual machines running their own guest operating system(s) and guest application software.

5

platforms.

- The server platform 20 may provide a variety of services to the virtual machines of the client platforms, for example, but not limited to, device virtualization/simulation services and virtual machine management services. A non-exhaustive list of examples for the client platform 10/30 may include mainframe computer, mini-computer, personal computer, portable computer,
- 15 laptop computer and other devices for transceiving and processing data. A non-exhaustive list of examples for the server platform 20 may include supercomputer, mainframe computer, workstation and other devices for transceiving and processing data.
- [0014] An embodiment of structures for the client platforms 10/30 and the server 20 20 in the virtual machine cluster environment 1 is shown in Fig. 2. The client platforms 10/30 and server platform 20 may be configured according to the hybrid virtual machine monitor architecture.
 - [0015] In the embodiment, each of the client platforms 10/30 may comprise an underlying hardware machine 11/31 having one or more processors, memory,
- 25 I/O devices, etc., wherein the I/O devices may further comprise a network

4

interface to transceive data through the network 40, such as the network interface 110 of the client platform 10 and the network interface 310 of the client platform 30.

[0016] Each of the client platforms 10/30 may further comprise a hypervisor (or micro-hypervisor) 12/32, which is a kernel component configured according to the hybrid virtual machine monitor architecture and responsible for processor(s)/memory virtualization, interrupt handling and domain scheduling. The hypervisor 12/32 may further comprise a network interface management core 120/320 to manage the network interface 110/310 of the underlying machine. Examples for the hypervisor may comprise Xen's hypervisor, Virtual PC's hypervisor, and the like.

software images running on a plurality of virtual machines created and managed by the hypervisor 12/32, for example, guest operating systems 131/141 and guest applications 132/142 running on the virtual machines 13/14 of the client platform 10, and guest operating systems 331/341 and guest applications 332/342 running on the virtual machines 33/34 of the client platform 30. The guest operating systems 131, 141, 331 and 341 may be different with each other. The number of guest operating systems running on the client platform may depend on utilization of processor/memory resources and device resources. For example, the number of guest operating systems may be low if the client platform utilizes the processor/memory resources more intensively compared to device utilization. However, the number of guest operating systems may be high if the client platform utilizes the device resources more intensively compared to processor/memory utilization.

15

20

Examples for the guest operating system may comprise Linux, Windows, FreeBSD Unix, etc.

- having one or more processors, memory, I/O devices, etc., wherein the I/O devices may further comprise a network interface 210 to transceive data through the network 40. The server platform 20 may be loaded with a service operating system 22 configured according to the hybrid virtual machine monitor architecture. The service operating system 22 may respectively interact with the hypervisors 12/32 of the client platforms 10/30 via the network 40 to service the plurality of virtual machines in the client platforms 10/30. Examples for the service operating system may comprise Linux, Windows, FreeBSD Unix, etc.
- [0019] The server platform 20 may be further loaded with a plurality of device models 23 and a control panel 24. The device models 23 may be virtual devices that may be created or defined for example according to the hybrid virtual machine monitor architecture. In some embodiments, because of device virtualization/simulation nature, the device models 23 may not be connected to or represented by a real instance of a device, and may not be reflected in a real device that is connected to a hardware component. Examples for the device models 23 may comprise, but not limited to, various I/O devices, an interrupt controller, an event timer, etc.
- [0020] The device models 23 may work with the service operating system 22 to provide device virtualization/simulation service to the virtual machines of the client platforms 10/30 via the network 40, including hosting device related operation from/to the virtual machines, such as device related I/O operation



and device model initiated interrupt. In some embodiments, the device models in the virtual machine cluster environment may be centralized in the server platform 20. However, in other embodiments, the client platform 10/30 may keep some of the device models, such as the device models frequently used by the virtual machines of the client platform. For example, the client platform 10/30 may keep the device models inside of the hypervisor 11/31.

The control panel 24 may work with the service operating system 22 to manage the virtual machines of the client platforms 10/30 via the network 40. In an embodiment, the control panel 24 may comprise a database 241 containing identifiers of the virtual machines (or the guest operating systems running on the virtual machines), the hypervisors and the client platforms in the virtual machine cluster environment that are served by the server platform 20; and as another possibility the database can be created or updated on fly. In an embodiment, a virtual machine of the client platform 10/30 may send a request for a device related input/output operation to the server platform 20 via the network 40. The control panel 24 and the service operating system 22 may identify a corresponding device model from the plurality of device models 23 to host the request, and further construct a feedback packet by incorporating a result of the input/output operation from the device model with identifier(s) to identify the virtual machine that has sent the operation request. In another embodiment, a device model may initiate an interrupt for a virtual machine of the client platform 10/30. The control panel 24 and the service operating system 22 may construct an interrupt packet by incorporating the interrupt instruction with identifier(s) to identify the virtual machine that may handle the interrupt. The identifier(s) may comprise a virtual machine identifier, a

25

20

5

10

15

[0021]

hypervisor identifier and/or client platform identifier. In addition, the control panel 24 may perform virtual machine management for other aspect, such as virtual machine operation management including virtual machine launching management, virtual machine shutdown management, virtual machine migration management, virtual machine suspend management, etc.

[0022] The server platform 20 may further be loaded with a plurality of application software running on the service operating system 22, such as applications 25 and 26.

5

25

Other embodiments may implement other technologies to the structure
depicted in Fig. 2. In an embodiment, the server platform 20 may further
comprise a hypervisor running between the underlying hardware machine 21
and the service operating system 22. In such case, the server platform 20 may
further comprise one or more virtual machine(s) defined by the hypervisor and
the service operating system. In another embodiment, console devices (e.g.,
frequently used input/output devices such as a keyboard, a mouse, a video
device, etc.) may be centralized in the underlying hardware machine 21 of the
server platform 20. In such case, the client platform 10/30 may not be provided
with the console devices.

[0024] Fig. 3 shows an embodiment of a method of implementing a device related input/output operation in the virtual machine cluster environment 1.

[0025] In the embodiment, an unauthorized input/output operation for inputting a data from a device (input operation) or outputting a data to the device (output operation) happens in a guest operating system running on a virtual machine of a client platform (e.g., guest operating system 131 running on the virtual machine 13 of the client platform 10), and a corresponding device driver in the

guest operating system may execute an 'IN' instruction for input operation or 'OUT' instruction for output operation, which may cause a trap into the hypervisor of the client platform in block 301, because the guest operating system is depriviledged.

5[0026] In block 302, the hypervisor of the client platform may perceive the unauthorized I/O operation happened in the guest operating system through a virtual machine exit, which is a transition from non-root VMX operation in the virtual machine to root VMX operation in the hypervisor.

10 request packet and send the packet to the server platform 20 through the network 40. In an embodiment, the I/O request may further comprise identifier(s) to identify a device model in the server platform 20 corresponding to the device that is related to the I/O operation in the guest operating system of the virtual machine. The identifier(s) may comprise a device model identifier and/or a server platform identifier (e.g., a network ID for the server platform). In response to receiving the I/O request packet, the service operating system 22 may identify the corresponding device model from the plurality of device models 23 under control from the control panel 24 and route the I/O request packet to the identified device model in block 304.

20[0028] In block 305, the identified device model may handle the I/O request. For output request, the data in the I/O request packet may be output to the identified device model. Depending upon inter-platform communication interface definition, the server platform 20 may send back a finish notification to the I/O requester (i.e., the client platform 10/30) to notify finish of the 'OUT' operation. However, for input request, the identified device model 23 may

obtain a feedback to the input request, for example, through cooperating with the service operating system 22 and the underlying hardware 21 of the service platform 20, and send a feedback packet to the service operating system 22 in block 306. The feedback packet may incorporate the feedback with identifier(s) to identify the guest operating system (or virtual machine) of the client platform that is executing the I/O operation. In an embodiment, the identifier(s) may comprise a guest operating system identifier (or virtual machine identifier) and/or a client platform identifier (e.g., a network ID for the client platform). In another embodiment, if the client platforms in the virtual machine cluster environment 1 comprises different types of hypervisors, e.g., Xen hypervisor, Virtual PC's hypervisor, etc., then the identifier may further comprise a hypervisor identifier to identify the different hypervisors.

5

10

[0029] In block 307, under control from the control panel stored with identifiers of the guest operating systems (or virtual machines), the hypervisors and the client platforms in the virtual machine cluster environment 1, the service operating system 22 may route the feedback packet to the client platform that has sent the I/O request based upon the identifier(s) in the feedback packet. In block 308, the hypervisor of the client platform may identify the guest operating system (or virtual machine) executing the corresponding I/O operation and send the feedback packet to the identified guest operating system through a virtual machine entry, which is another transition from the root VMX operation in the hypervisor to the non-root VMX operation in the virtual machine.

[0030] An embodiment of a method of implementing a device model initiated interrupt in the virtual machine cluster environment 1 is shown in Fig. 4.

- [0031] In block 401, one of the device models 23 in the server platform 20 initiate an interrupt for a guest operating system of a client platform in the virtual machine cluster environment 1. In block 402, the device model passes an interrupt packet incorporating the interrupt instruction as well as identifier(s) to identify the guest operating system (or virtual machine) of the client platform to the service operating system 22. In an embodiment, the identifier(s) may comprise a guest operating system identifier (or virtual machine identifier) and/or a client platform identifier (e.g., a network ID for the client platform). In another embodiment, if the client platforms in the virtual machine cluster environment 1 comprises different types of hypervisors, e.g., Xen hypervisor, Virtual PC's hypervisor, etc., then the identifier may further comprise a hypervisor identifier to identify the different hypervisors.
- [0032] In block 403, under control from the control panel 24, the service operating system 22 may send the interrupt packet to the client platform identified by the identifier(s) in the interrupt packet. The hypervisor of the client platform may further identify the guest operating system based upon the interrupt packet and inject the interrupt to the identified guest operating system through the virtual machine entry (block 404), so that the guest operating system may handle the interrupt (block 405).
- 20[0033] Fig. 5 shows an embodiment of a computer platform that may be implemented as a platform in the virtual machine cluster environment 1.
- [0034] In an embodiment, the computing platform may comprise one or more processors 50, memory 51, chipset 52, I/O device 53, BIOS firmware 54 and the like. The one or more processors 50 are communicatively coupled to various components (e.g., the memory 51) via one or more buses such as a

processor bus. The processors 50 may be implemented as an integrated circuit (IC) with one or more processing cores that may execute codes under a suitable architecture, for example, including Intel® XeonTM, Intel® PentiumTM, Intel® ItaniumTM architectures, available from Intel Corporation of Santa Clara, California.

[0035] In an embodiment, the memory 51 may store codes to be executed by the processor 50. A non-exhaustive list of examples for the memory 51 may comprise one or a combination of the following semiconductor devices, such as synchronous dynamic random access memory (SDRAM) devices,

- 10 RAMBUS dynamic random access memory (RDRAM) devices, double data rate (DDR) memory devices, static random access memory (SRAM), flash memory devices, and the like.
- [0036] In an embodiment, the chipset 52 may provide one or more communicative path among the processor 50, memory 51 and various components, such as the I/O device 53, peripheral component 54, and BIOS firmware 55. The chipset 52 may comprise a memory controller hub 520, an input/output controller hub 521 and a firmware hub 522.
- [0037] In an embodiment, the memory controller hub 520 may provide a communication link to the processor bus that may connect with the processor 50 and to a suitable device such as the memory 51. The memory controller hub 520 may couple with the I/O controller hub 521 that may provide an interface to the I/O devices 53. A non-exhaustive list of examples for the I/O devices 53 may comprise a keyboard, a mouse, a storage device, a video device, an audio device, a network interface, and the like.

[0038] In an embodiment, the memory controller hub 520 may communicatively couple with a firmware hub 522 via the input/output controller hub 521. The firmware hub 522 may couple with the BIOS firmware 54 that may store routines that the computing platform executes during system startup in order to initialize the processors 50, chipset 52, and other components of the computing platform. Moreover, the BIOS firmware 54 may comprise routines or drivers that the computing platform may execute to communicate with one or more components of the compute platform.

[0039] In an embodiment, the computer platform as depicted in Fig. 5 may perform as a client 10/30. The memory 51 may store software images such as a hypervisor, guest operating systems, guest applications, etc. In another embodiment, the computer platform as depicted in Fig. 5 may perform as a server platform 20. The memory 51 may store software images such as a service operating system, device models, control panel, and optionally various applications, etc.

[0040] Another embodiment for the server platform and client platform structures in the virtual machine cluster environment 1 is depicted in Fig. 6. As depicted, more than one server platforms (e.g., owner server platform 620 and I/O server platform 6200) may connect with the client platform 10/30 through the network 40 to provide them with device virtualization/simulation services. The owner server platform 620 has similar structure as the server platform 20 and the I/O server platform 6200 is loaded with a plurality of device models 6230 so that the server platforms 620/6200 may provide robust device virtualization services to their client platforms. Functionalities of the control panel 624 may encompass management of the device models 6230 in the I/O server platform

6200. In an embodiment, the control panel 624 may perform the device model identification based upon an I/O request packet from the client platform 10/30. In such case, the owner server platform 620 may first receive the I/O request packet from the client platform 10/30 via the network 40 and route the I/O request packet to the device model 6230 in the I/O service platform 6200 after analyzing the identifier(s) in the I/O request packet. In another embodiment, the device model 6230 may construct an I/O feedback packet or an interrupt packet by incorporating an identifier(s) to identifier the guest operating system (or virtual machine) in the intended client platform 10/30 under supervision from the control panel 624.

5

10

[0041] While certain features of the invention have been described with reference to example embodiments, the description is not intended to be construed in a limiting sense. Various modifications of the example embodiments, as well as other embodiments of the invention, which are apparent to persons skilled in the art to which the invention pertains are deemed to lie within the spirit and scope of the invention. For example, although the above embodiments are described according to the hybrid virtual machine monitor architecture, the present invention may be applied to other kinds of virtual machine monitor architectures, such as a host virtual machine monitor.

What is claimed is:

5

15

20

1. A method for a client platform coupled to a server platform via a network, comprising:

determining that an input/output operation related to a hardware device happens in a virtual machine of the client platform; and

requesting the server platform via the network to handle the input/output operation related to the hardware device.

- 2. The method of claim 1, wherein the request comprises a server identifier to identify the server platform.
 - 3. The method of claim 1, wherein the request comprises a software device identifier to identify a software device from a plurality of software devices in the server platform to handle the input/output operation related to the hardware device.
 - 4. The method of claim 1, further comprising:

receiving a feedback for the input operation from the server through the network, the feedback comprising a virtual machine identifier to identify the virtual machine in the client platform that is executing the input operation; and

sending the feedback to the virtual machine identified by the virtual machine identifier.

5. The method of claim 1, further comprising:

5

10

15

20

receiving via the network an interrupt instruction issued by a software device of the server platform, the interrupt instruction comprising a virtual machine identifier to identify a virtual machine to perform the interrupt instruction; and

injecting the interrupt instruction into the virtual machine identified by the virtual machine identifier.

6. A machine-readable medium comprising a plurality of instructions which when executed result in a client platform:

determining that an input/output operation related to a hardware device happens in a virtual machine of the client platform; and

requesting a server platform coupled to the client platform via the network to handle the input/output operation related to the hardware device.

- 7. The machine-readable medium of claim 6, wherein the request further comprise a server identifier to identify the server platform.
- 8. The machine-readable medium of claim 6, wherein the request comprises a software device identifier to identify a software device from a plurality of software devices in the server platform to handle the input/output operation related to the hardware device.



9. The machine-readable medium of claim 6, wherein the plurality of instructions further result in the client platform:

receiving a feedback for the input operation from the server platform through the network, the feedback comprising a virtual machine identifier to identify the virtual machine in the client platform that is executing the input operation; and

5

25

sending the feedback to the virtual machine identified by the virtual machine identifier.

10. The machine-readable medium of claim 6, wherein the plurality of instructions further result in the client platform:

receiving an interrupt instruction issued by a software device from the plurality of software devices in the server platform through the network, the interrupt instruction comprising a virtual machine identifier to identify a virtual machine to perform the interrupt instruction;

injecting the interrupt instruction to the virtual machine identified by the virtual machine identifier.

11. A method for a server platform coupled to a client platform via a20 network,

receiving, from the client platform via the network, a request for an input/output operation related to a hardware device; and

identifying a software device from a plurality of software devices in the server platform to handle the request, the identified software device corresponding to the hardware device related to the input/output operation.



- 12. The method of claim 11, wherein the request comprises a software device identifier to identify the software device in the server platform.
 - 13. The method of claim 11, further comprising

receiving the request for the input/output operation with a first server of the server platform,

determining whether the identified software device is in a second server of the server platform; and

sending the request from the first server to the second server via the

network, in response to determining that the identified software device is in the
second server.

14. The method of claim 11, further comprising:

15

obtaining a result for the input operation from the identified software device;

constructing a feedback with the result and a virtual machine identifier to identify a virtual machine in the client platform that is executing the input operation; and

sending the feedback from the server platform to the client platform through the network.

- 20
 15. The method of claim 14, wherein the feedback further comprise a client platform identifier to identify the client platform that has sent the request.
 - 16. The method of claim 11, further comprising:

25 issuing an interrupt instruction from a software device of the plurality of software devices in the server platform to the client platform through the network.



- 17. The method of claim 11, wherein the interrupt instruction further comprises a virtual machine identifier to identify a virtual machine in the client platform to handle the interrupt.
- 18. A machine-readable medium comprising a plurality of instructions which when executed result in a server platform:

receiving a request for an input/output operation related to a hardware device from a client platform through a network; and

identifying a software device from a plurality of software devices in the

server platform to handle the request, the identified software device corresponding
to the hardware device related to the input/output operation.

19. The machine readable medium of claim 18, wherein the request comprises a software device identifier to identify the software device in the server platform.

15

- 20. The machine readable medium of claim 18, wherein the plurality of instructions that result in the server platform receiving the request, further result in the server platform:
- receiving the request for the input/output operation from the client platform with a first server in the server platform.

21. The machine readable medium of claim 20, wherein the plurality of instructions further result in the server platform:

determining whether the identified software device is in a second server of the server platform; and

sending the request from the first server to the second server through the network, in response to determining that the identified software device is in the second server.

22. The machine readable medium of claim 18, wherein the plurality ofinstructions further result in the server platform:

5

15

obtaining a result for the input operation from the identified software device; constructing a feedback with the result and a virtual machine identifier to identify a virtual machine in the client platform that is executing the input operation; and

sending the feedback from the server platform to the client platform through the network.

- 23. The machine readable medium of claim 22, wherein the feedback further comprise a client identifier to identify the client platform that has sent the
 request.
 - 24. The machine readable medium of claim 18, wherein the plurality of instructions further result in the server platform:

issuing an interrupt instruction from a software device of the plurality of software devices in the server platform to the client platform through the network.

- 25. The machine readable medium of claim 24, wherein the interrupt instruction further comprises a virtual machine identifier to identify a virtual machine in the client platform to handle the interrupt.
- 5 26. A system, comprising

- a client platform comprising:
- a plurality of virtual machines; and
- a virtual machine monitor to determine that an input/output operation related to a hardware device happens in a virtual machine of the plurality of virtual machines and construct a request for the input/output operation;
 - a client network interface to send the request through a network; and the server platform comprising:
 - a server network interface to receive the request through the network;
 - a plurality of software devices;
- a controller to identify a software device from the plurality of software devices to handle the request, the identified software device corresponding to the hardware device related to the input/output operation.
- 27. The system of claim 26, wherein the request further comprises asoftware identifier to identifier the software device in the server platform.

28. The system of claim 26, wherein

the identified software device in the server platform is further to obtain a result for the input operation, and construct a feedback with the result and a virtual machine identifier to identify the virtual machine in the client platform under control from the controller, and

the server network interface is further to send the feedback to the client platform through the network.

29. The system of claim 26, wherein

5

10

15

20

the client network interface is further to receive a feedback for the input operation from the server platform through the network; and

the virtual machine monitor is further to identify the virtual machine in the client platform that is executing the input operation based upon the feedback and send the feedback to the identified virtual machine.

30. The system of claim 26, wherein

a software device in the server platform is to issue an interrupt instruction under control from the controller, the interrupt instruction including a virtual machine identifier to identify another virtual machine in the client platform to handle the interrupt instruction; and

the server network interface is further to send the interrupt instruction to the client platform through the network.

31. The system of claim 30, wherein

5

10

15

the client network interface is further to receive the interrupt instruction; and the virtual machine monitor is further to identify the another virtual machine from the plurality of virtual machines based upon the interrupt instruction and inject the interrupt into the identified another virtual machine.

32. A method for a system comprising a client platform and a server platform, wherein the client platform couples to the server platform through a network, the method comprising:

determining that an input/output operation related to a hardware device happens in a virtual machine of the client platform;

sending a request for the input/output operation from the client platform to the server platform through the network;

receiving the request through the network by the server platform; identifying a software device from a plurality of software devices in the server platform to handle the request, wherein the identified virtual device corresponds to the hardware device related to the input/output operation.

33. The method of claim 32, wherein the receiving further comprisesreceiving the request with a first server in the server platform.



34. The method of claim 33, further comprising:

determining whether the identified software device is in a second server of the server platform; and

sending the request from the first server to the second server through the network, in response to determining that the identified software device is in the second server.

35. The method of claim 32, further comprising:

15

obtaining a result for the input operation from the identified software device in the server platform;

constructing a feedback with the result and a virtual machine identifier to identify the virtual machine in the client platform that is executing the input operation; and

sending the feedback from the server platform to the client platform through the network.

- 36. The method of claim 35, wherein the feedback further comprise a client identifier to identify the client platform that has sent the request.
- 37. The method of claim 32, further comprising: issuing an interrupt instruction from a software device in the server platform to the client platform through the network.
- 38. The method of claim 32, wherein the interrupt instruction further
 comprises a virtual machine identifier to identify another virtual machine in the
 client platform to handle the interrupt.



39. The method of claim 38, further comprising:

receiving the interrupt instruction through the network by the client platform;

identifying the another virtual machine in the client platform based upon the interrupt instruction; and

5 injecting the interrupt into the identified another virtual machine.




ABSTRACT


5

10

Machine-readable media, methods, apparatus and system are described. In some embodiments, a client platform may determine that an input/output operation related to a hardware device may happen in a virtual machine of the client platform and request a server platform via the network to handle the input/output operation related to the hardware. The server platform may receive the request from the client platform through the network; and identify a software device from a plurality of software devices in the server platform to handle the request, wherein the identified software device corresponds to the hardware device related to the input/output operation.



FIG



(




FIG. 3






FIG. 4




FIG. 5

